

ENGINEERING DEPARTMENT.

BANGALORE DIVISION.

Notification dated 21st October 1932.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M., on 14th November 1932, for restoring Breached Marasandra Amanikere, Registered No. 463a of Bangalore Taluk.

An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1933.

2. The plans, detailed estimates and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 300 (three hundred) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Breached Marasandra Amanikere, Registered No. 463a of Bangalore Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Percentage rates above or below the estimate amount will not be accepted.

10. No claims for enhanced rates will be entertained on any account after acceptance of tenders.

11. The Contractor will be dealt with in terms of the bond for any short progress or delay. In matters of all disputes about rates and measurements, quality of work, etc., and in all disputes of any kind, the decision of the Chief Engineer, will be final and legally binding on the Contractor.

12. Rates should be quoted both in words and figures for each item of works and lumpsum provisions are subject to modifications as per data worked out during execution. For individual items of work under lumpsum provisions, the rates tendered for similar items of works will be paid and for other items, the rates as per schedule of rates will be paid at the discretion of the Executive Engineer.

13. Rates for masonry include bond stones to the required percentage at the required intervals of the quality and size to be specified.

Abstract.

No.	Items of work	Unit	Rate	Quantity	Cost
	Bund. R. L. 53.00 Top width 4½' to 6' at Breach portion.—		Rs.		Rs.
1	Cutting girps and clearing jungle ...	Grade.		24	
2	Earth work to breach with watering and tamping including lead and lift.	Cyds.		2,680	
3	Lead and lift for earth available from approach clearing.	"		3,806	
4	Clearing sand and silt ...	"		1,076	
5	Puddle wall mixed with gravel in breach ...	"		372	
6	New stone revetment ...	"		974	
7	Turfing ...	Syds.		181	
8	Providing new grade stone with figuring and numbering.	Each		25	
9	Do Index stones ...	"		25	
10	Do Registered No. and wake stone ...	"		1	
11	Do B. M. stone ...	"		2	
12	Do Gauge stone ...	"		1	

No.	Items of work	Unit	Rate	Quantity	Cost
	Sluice—		Rs.		Rs.
	Cut opening the bund and constructing a masonry sluice as per type design.	...	...	...	...
1	Cutting open the bund and refilling it after constructing the new sluice.	Cyds.		258	
2	Earth work excavation for foundation	...		22	
3	Concrete in surki mortar	C.ft.		190	
4	Burnt brick in surki mortar	...		1,118	
5	Burnt stone slabs 6" thick dressed	S.ft.		378	
6	Plastering with surki mortar	Sqr.		5.76	
7	Pointing do	...		1.26	
8	Cutting holes in slabs	Each		6	
9	Cutting holes in orifice slabs	"		2	
10	Providing teak wood plug with iron rod including locking arrangements,	"		2	
11	Rectifying the rough stone work by the side of the wing.	L. S.		2	
	Waste weir L. R. 48'00 and 640 ft. long:—				
1	Earth work	Cyds.		8,562	
2	Burnt brick in surki mortar	C.ft.		1,118	
3	Burnt stone slabs 6" thick dressed	S.ft.		292	
4	Rough stone work, new	Cyds.		148	
5	Plastering with surki mortar	Sqr.		11.00	
6	Joggle joints, 8' apart	...			

N. G. KRISHNA IYENGAR,
Executive Engineer.

GOVERNMENT OF MYSORE, ELECTRICAL DEPARTMENT.

CONSTRUCTING ELECTRICAL BUILDINGS AT MULBAGAL TOWN AND AT DEVANHALLI TOWN.

Attention is invited to notification dated 3rd October 1932, published in pages 1117 and 1118, Part VI of the *Mysore Gazette*, dated 13th October 1932, calling for tenders for the above works. The latest date for receiving tenders is 29th October 1932.

V. R. COWSIK,
For Chief Electrical Engineer.

KOLAR DIVISION.

Abstract Notification dated 6th October 1932.

The attention of the public is invited to the advertisement in the *Mysore Gazette*, dated 13th October 1932, pages 1121 and 1122, Part VI, calling for tenders for the work of Restoring Yeldur Santhemmanakere, Srinivasapur Taluk.

The last date of receipt of tender is 2nd November 1932.

Abstract Notification dated 6th October 1932.

The attention of the public is invited to the notification published in pages 1122 and 1123, Part VI of the *Mysore Gazette*, dated 13th October 1932, calling for tenders for the work of Restoring Vakkaleri Durgikere, Regd. No. 205 of Kolar Taluk.

The last date fixed for receipt of tender is 1st November 1932.

C. T. NAKASIMHA IYENGAR,
Executive Engineer.

TUMKUR DIVISION.

Abstract Notification dated 1st—2nd October 1932.

SUBJECT—Improving the regulation of water under Gubbi Amanikere, Registered No. 3 of Gubbi Taluk.

The attention of the public is drawn to notification calling for tenders for the above work in pages 1125 and 1126 of part VI of the *Mysore Gazette*, dated 13th October 1932.

2. The tenders will be received by the Executive Engineer, Tumkur Division, Tumkur, up to 3 P.M. of 2nd November 1932.

3. An earnest money of Rs. 300 should accompany the tender.

A. TANDONI RAO,
Executive Engineer.

SHIMOGA DIVISION.

Notification dated 21st October 1932.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 14th November 1932, for Restoring Hebbandi Chikkere, unrestored minor tank in Shimoga Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1933.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 250 in cash or Government Promissory Notes as earnest money and be superscribed "Tender for Restoring Hebbandi Chikkere, unrestored minor tank in Shimoga Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates should be quoted for each item of work both in words and figures.

10. Tenders which quote rates as "estimated rates" or "some per cent more or less" will not be considered.

11. No claims for enhanced rates will be entertained on any account after acceptance of tender.

12. For all lumpsum provisions detailed measurements will be taken and tendered items will be paid at tendered rates and fresh claims paid at the current scheduled rates.

13. The accepted tenderer is bound to execute the work to the extent of grant sanctioned.

14. Any unforeseen items found necessary during execution will be paid at current scheduled rates.

15. In all matters of the dispute regarding quality of the work and rates, the decision of the Superintending Engineer, Shimoga Circle, is final and legally binding.

Abstract estimate of quantities for tender for restoring Hebbandi Chikkere R. No. 672, Shimoga Taluk (Bhadravati Hobli).

No.	Description of work	Unit	Quantity	Rate	Amount
	<i>Bund Top width 4½' R.L. 56'50.</i>			Rs.	Rs.
1	Jungle clearing and cutting grips, etc., in the old bund.	Lump	sum		
2	Earthwork to bund including carrying, watering and tamping, etc., complete.	C.yd.	5,638		
3	Turfing the front and rear slopes of bund	Sqr.	4'16		
4	Providing grade stones on a bed of concrete 1' x 1' x 1'.	Each	13		
5	Do do Index do	"	13		
6	Do do B. M. Stones	"	2		
7	Do do Register No. and date stone.	"	1		

No.	Description of work	Unit	Quantity	Rate	Amount
	<i>Constructing a pipe sluice No. 1 at C. S. No. 3 R. L. 47'00 dia 6".</i>			Rs.	Rs.
1	Cutting open the bund to R. L. 47'00 to a width of 7' and refilling the same including consolidation.	C.yd.	33		
2	Excavating foundation		8		
3	Stone jelly concrete in surki mortar	C.ft.	207		
4	Size stone masonry in surki mortar	"	222		
5	Burnt stone slabs 6" thick dressed and fixed	S.ft.	53		
6	Cement plastering $\frac{1}{2}$ " thick	Lump	sum		
7	Pointing with surki mortar	Sqr.	3'00		
8	Fixing Bhadravati cast iron pipe 6" dia. including Ry. freight and carting. The pipes being supplied at Bhadravati by the department.	R.ft.	30		
9	Providing teakwood plug with iron rod including locking arrangements, etc., complete.	Lump	sum		
10	Cutting orifice holes in stone slabs.	Lump	sum		
	<i>Constructing a masonry weir left flank 70' long R. L. 52'00.</i>				
1	Earthwork excavation for foundation	C.yd.	58		
2	Stone jelly concrete in surki mortar	C.ft.	298		
3	Size stone masonry in surki mortar	"	894		
4	Cement concrete slabs 6" thick cast in one piece plastered over.	"	65		
5	Pointing with surki mortar	Sqr.	6'00		
6	Rough stone work	C.yd.	114		
	<i>Constructing a pipe sluice No. 2 at C. S. 8 at R. L. 46'50 dia 7".</i>				
1	Earthwork cutting open bund and refilling the same with consolidation.	C.yd.	27		
2	Earthwork excavation	"	8		
3	Stone jelly concrete in surki mortar	"	222		
4	Size stone masonry in surki mortar	"	264		
5	Burnt stone slabs 6" thick dressed and fixed	S.ft.	54		
6	Cement plastering $\frac{1}{2}$ " thick	Lump	sum		
7	Pointing with surki mortar	Sqr.	3'00		
8	Fixing C. I. pipe 7" dia including Ry. freight and carting, the pipes being supplied at Bhadravati by department.	R.ft.	30		
9	Plug with iron rod including locking arrangements, etc., complete.	Lump	sum		
10	Cutting orifice holes	Lump	sum		

Dated 19th October 1932.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 14th November 1932, for restoring Ubrani Beeranakatte R. No. 235, Channagiri Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1933.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 125 in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for restoring Ubrani Beeranakatte R. No. 235, Channagiri Taluk, Shimoga District," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates should be quoted for each item of work both in words and figures.

10. Tenders which quote rates as "estimated rates" or "some per cent more or less" will not be considered.

11. No claims for enhanced rates will be entertained on any account after acceptance of tender.

12. For all lump-sum provisions detailed measurements will be taken and tendered items will be paid at tendered rates and fresh claims paid at the current scheduled rates.

13. The accepted tenderer is bound to execute the work to the extent of grant sanctioned.

14. Any unforeseen items found necessary during execution will be paid at current scheduled rates.

15. In all matters of the dispute regarding quality of the work and rates, the decision of the Superintending Engineer, Shimoga Circle, is final and legally binding.

Abstract of estimated quantities for tender for restoring Ubrani Beerankatte R. No. 235, Channagiri Taluk, Shimoga District.

No.	Items of work	Unit	Quantity	Rate	Amount
	<i>Bund R. L. 56'00 Top width 4½ feet.</i>			Rs.	Rs.
1	Jungle clearing cutting grips, etc., complete.	Lumpsum			
2	Earthwork to bund including excavating and carrying and consolidation with watering.	Cyd.	1,473		
3	Turfing front and rear slopes ...	Sqr.	146		
4	Providing and fixing grade stones with 1' x 1' x 1' surki concrete.	Each	10		
5	Do Do Index stones ...	"	10		
6	Date and Register No. stone ...	"	1		
7	Fixing B. M. stone with 2' x 2' x 2' surki concrete.	"	2		
	<i>Constg. a C. I. Pipe sluice of 6" dia, at R. L. 44'00 at cross section No. 8.</i>				
1	Earthwork excavating foundation ...	Cyd.	60		
2	Refilling and consolidating after construction.	"	59		
3	Stone jelly concrete in surki mortar ...	"	164		
4	Size stone in surki mortar ...	Cft	290		
5	Burnt stone slabs 4½" to 6" thick dressed and fixed.	Sft.	36		
6	Cement concrete 6" thick plastering ...	Cft.	6		
7	Pointing in surki mortar ...	Sqr.	3'00		
8	Cutting orifice holes ...	Lumpsum			
9	C. I. Pipe 8" dia. including Ry. freight, carting to work spot and fixing with cement joint, etc., complete. The pipes being supplied by Department at Bhadravati.	Rft.	36		
10	Teak wood plug with iron rod including locking arrangements, etc.	Lumpsum			
	<i>Constg. a waste weir 80' long R. L. 52'00</i>				
1	Draft clearing ...	Lumpsum			
2	Earthwork excavating foundation ...	Cyd.	102		
3	Stone jelly concrete in surki mortar ...	Cft.	326		
4	Size stone in surki mortar ...	"	671		
5	Cement concrete slabs 6" thick cast in one piece and plastered over.	"	73		
6	Burnt stone slabs 6" thick dressed and fixed.	Sft.	128		
7	Surki mortar pointing ...	Sqr.	3'00		
8	Jaggle joints ...	...	L S		
9	Rough stone work ..	Cyd.	70		